





NOTE:
 DRAWINGS INDICATE THE BASIC REQUIREMENTS AND MINIMUM EROSION CONTROL MEASURES FOR THE PROJECT. CONTRACTOR SHALL BE RESPONSIBLE TO ADJUST MEASURES AND/OR INSTALL ADDITIONAL MEASURES AS NECESSARY FOR EARTHWORK OPERATIONS AND PHASING OF CONSTRUCTION, INCLUDING PROTECTING EXISTING IMPROVEMENTS DURING CONSTRUCTION PHASING IN ACCORDANCE WITH RULE 5 REQUIREMENTS AND CITY OF SOUTH BEND REGULATIONS.
 CONTRACTOR SHALL INSPECT SITE AND ALL EROSION CONTROL MEASURES WITHIN 24 HRS AFTER EACH ONE-HALF INCH RAIN EVENT AND MAKE ANY NECESSARY REPAIRS OR ADJUSTMENTS. CONTRACTOR SHALL SUBMIT REQUIRED WRITTEN REPORTS TO CITY OF SOUTH BEND MS-4 COORDINATOR AND COPY TO ARCHITECT.

- LEGEND - EROSION CONTROL**
-  DESIGNATED AREAS:
 - TRASH DISPOSAL AREA
 - FUEL STORAGE/FUELING AREA
 - CONCRETE WASH OUT AREA
 DESIGNATED AREA IS APPROXIMATE IN LOCATION AND SIZE. CONTRACTOR MAY RELOCATE AND/OR ADJUST SIZE AS NECESSARY FOR CONSTRUCTION ACTIVITIES. ALL DESIGNATED AREAS TO MEET LOCAL, STATE AND FEDERAL REGULATIONS FOR HAZARDOUS MATERIALS AND SAFETY.
 -  GRAVEL CONSTRUCTION ENTRANCE/EXIT PAD. CONTRACTOR MAY RELOCATE AS NECESSARY FOR CONSTRUCTION PHASING
 -  EROSION CONTROL BARRIER
 - SILT FENCE ROW
 -  INLET / CATCH BASIN PROTECTION

SITE PLAN
 1" = 20'-0"
 NORTH

SWPPP PLAN

8/8/2016 3:13:59 PM